

**City of Decatur Building Department
172 N 2nd St
Decatur Indiana 46733**

**Roger W. Gage
Superintendent**

office 260.724.3814
fax 260.724.9104

**ALL INSPECTIONS
REQUIRE 24-HOUR NOTICE**

- | | |
|--|--|
| 1. Lot Lines, Layout | When staked, prior to excavation |
| 2. Footing Inspection,
Including Post Holes | After excavation and foam is in place,
before pouring concrete |
| 3. Foundation Inspection | Crawl Space - after foundation walls are poured or
block is laid |
| 4. Underslab Plumbing
and Heating | Prior to covering with fill |
| 5. Slab Inspection | Prior to pouring building slab or basement floor
(after wire and vapor barrier are installed) |
| 6. Rough Electrical | Before enclosing walls with insulation, wall board,
paneling, etc. |
| 7. Rough Plumbing | Before enclosing walls with insulation or wall board |
| 8. Rough Heating | Before enclosing walls with insulation or wall board |
| 9. Framing | After mechanical, plumbing, and electrical system
is installed and before enclosing walls with insulation or
wall board |
| 10. Draft Stopping | Before enclosing walls with insulation |
| 11. Electrical Service | Prior to electric company hook up.
Buried Services Entrances require final grading of lot. |
| 12. Sidewalks | WHEN FORMED, PRIOR to pouring. |
| 13. Final Inspection | PRIOR TO OCCUPANCY OF STRUCTURE |

bldg4